JIMEN POWER Perkins* Diesel Power Diesel Power

60Hz

114.4 KVA 3 PHASE

GENERATING SET MODEL JP-100		
Output Ratings	Prime	Standby
380-415 V, 3 ph, 50 Hz, 1500 rpm	100 KVA	110 KVA
	80 KW	 88 KW
380-415 V, 3 ph, 60 Hz, 1800 rpm	114.4 KVA	126.5 KVA
	90 KW	100 KW

ENGINE/ TECHNICAL DATA

100 KVA

3 PHASE 50Hz

		Ratings at 0.8 Power Factor
Engine Make	Perkins	3
Engine Model	1104A-4	14TAG2
Governing Type	Electro	nic
Number of Cylinders	4	
Cylinder Arrangement	Vertical in	line
Bore and Stroke mm	105 X 1	127
Displacement/ Cubic Capacity litres	4.41	<u> </u>
Induction System	Turbocha	rged, air to air
Cycle	4 strok	(e
Combustion System	Direct Injection	
Compression Ratio	18.2:1	
Frequency and Engine Speed 50	Hz & 1500rpm	60Hz & 1800rpm
Gross Engine Power kW(hp)		
Fuel Consumption @50% load L/hr	11.2	
@75% load L/hr	17.1 22.6	24.9
@100% load L/hr		
Total Lubrication System Capacity litres	8	8
Total Coolant Capacity (inc. radiator) litres	12.6	12.6
Exhaust Temperature: °C	514	543

ALTERNATOR DATA			
Make	UPS/ Leroy Somer		
Model	UPS274C/LSA (TAL) 44D		
No. of Bearings	1		
Insulation class	Н		
Wires	6/12		
Ingress Protection	IP23		
Excitation System	Shunt		
Winding Pitch	2/3		
- ·	0070 (
Overspeed	2250 mn ⁻¹		
Voltage Regulation	n (steady) ±1%		
CONTROL PANEL			
Make	DeepSea		
Model	4000 Series		

The **DSE 4000** series is an Auto Start Control Module for single genset applications. It includes a backlit LCD display which clearly shows the status of the engine all the times. This module can either be programmed using the front panel or by using the DSE configuration suite PC software.

Metering and Alarm Indications:

Generator frequency
Underspeed, Overspeed
Generator volts (L-L-L-N)

- Generator current
- Engine oil pressure
 - Engine coolant temperature
 - Hours run counter
 - Battery volts
 - Fail to start/stop
 - Emergency stop
 - Failed to reach loading voltage/frequency
 - Charge fail Low DC Voltage
 - CAN diagnostics and CAN fail/error

Image is for Illustrative purpose only





STANDARD SPECIFICATIONS

100 KVA 3 PHASE 50Hz

1. ENGINE

Perkins four stroke heavy duty high performance industrial type diesel engine

2. ENGINE FILTRATION SYSTEM

- Cartridge type dry air filter.
- Two cartridge type fuel filter.
- Full flow lube oil filter. All filters have replaceable elements.

3. COOLING RADIATOR

Radiator and cooling fan, complete with safety guards designed to cool the engine at high ambient temperatures (consult your dealer for de-ration factors)

4. EXHAUST SYSTEM

Exhaust gas flow	313 (m3/min)	
Maximum allowable back pressure	18.0 (kPa)	

5. CIRCUIT BREAKER TYPE


3 pole MCCB. (4 pole is optional)


6. FUEL SYSTEM

The baseframe design is incorporated with an integral fuel tank with a capacity of approx.. 8 hours running at Full load. The tank is supplied complete with fill cap breather, fuel feed and return lines to the Engine and the drain plug


STANDARD GENERATOR DIMENSION AND WEIGHT

Silent Type (with Soundproof Canopy)





Open Type (without Soundproof Canopy)



7. ALTERNATOR

7.1 INSULATION SYSTEM

- The insulation system is Class H.
- All windings are impregnated in either a triple dip thermoset-Ting liquid, oil and acid resisting polyester varnish or vacuum pressure impregnated with a special polyester resin.
- Heavy coat of antitracking varnish additional protection Against moisture or condensation.

7.2 AUTOMATIC VOLTAGE REGULATOR (AVR)

The fully sealed Automatic Voltage Regulator maintains

The Voltage Regulation at ±1%. Nominal adjustment by means of a trim pot incorporated on the AVR.

8. MOUNTING ARRANGEMENT

8.1 COUPLING

The Engine and Alternator are directly coupled by means of an SAE flange. The Engine flywheel is flexibly coupled to the Alternator rotor

8.2 ANTI-VIBRATION MOUNTING PADS

Anti-Vibration pads are affixed between tae Engine/Alternator feet and the Baseframe thus ensuring complete vibration isolation of the rotating assembly.

8.3 SAFETY GUARDS

The Fan & Fan Drive along with the battery Charging Alternator are Safety Guard protected for personnel protection.

330

114.4 KVA

3 PHASE

9. FACTORY TEST

60Hz

- The Generating set is load tested before dispatch
- · All protective devise control functions and site load conditions are simulated. The generator and its systems are checked before dispatch.

10. EQUIPMENT FINISHING

All mild steel components are fully degreased and painted with powder coated paint to ensure maximum scuff resistance and durability

11. DOCUMENTATION

Operation & Maintenance manual, Circuit wiring diagrams and Commissioning/ Fault Finding instruction leaflets are accompanied with the Generator.

12. QUALITY STANDARDS

The equipment meets the following standards, BS4999, BS5000, BS5514 IEC 60034, VDE0530, NEMA MG 1.22 and ISO 8528

13. WARRANTY

-640.00 -640.00-

550


1 h

All of the Generating sets are covered under a warranty policy For a period of 12 months or 1000 working hours. Warranty of the equipment is in line with manufacturers warranty terms & conditions. (check warranty statement for more details, as it may vary for different countries.)

In line with the continuous product development, we reserve The right to change specifications without notice.

1330.00

E-mail: info@jimenpower.com Web: www.jimenpower.com



-1100.00-